



Upper Saucon Township Municipal Authority

4774 Saucon Creek Road, Center Valley, PA 18034

Attention Inspection Services

Camera Instructions

It is necessary for Upper Saucon Township Municipal Authority provide instructions for lateral videos due to number of observed issues. Please read the instructions carefully contact office if it is unclear what is expected. It is the contractor's responsibility to inspect the lateral but not to certify sewer lateral for USTMUA. If instructions are not followed, the contractor will be responsible for the cost of and redo the inspection video – not the homeowner. Instruction for video inspection are as follows:

1. **The contractor will supply a USB video to the homeowner, realtor, closing company or drop off video to the Upper Saucon Township Municipal Authority office.**
2. The camera equipment used shall be specifically designed and constructed for such inspections. Equipment capable of adding notes or observations is preferred.

(ONLY USB VIDEOS WILL BE ACCEPTED)
3. Lighting shall be sufficient to provide clear illumination of the entire perimeter of the pipe for several feet ahead and video must be clear enough to recognize pipe material and/or defects.
4. The video shall show the area around the point of entry in order to confirm the location as well as a clear image of the cleanout or the sewer main at the end of the survey. **(SHOW HOUSE & NUMBER)**
5. Video shall be from the **building wall to the sewer main**. If for any reason you cannot finish the inspection, it will be given back for completion.
6. The camera shall be pushed or pulled in as nearly continuous a motion as practicable, without skipping any portions of pipe. It shall also be pushed or pulled no greater than **30 feet per minute and shall be stopped to observe features such as joints, defects, branch connections or irregularities of any kind and shall be slowly advanced back and forth as needed to provide as full a view of any features as possible.**
7. Digital recordings submitted to the Authority must be in MP4 format, legibly labeled with the time, date, and address of the recorded session accompanied by the **Completed** Sanitary Sewer Lateral Inspection Report (more information is better than an incomplete report). which can be included on USB or printed separately.

Note: ORDINANCE # 42-U Permits video inspection oversight by the Superintendent or their designee.

Failure to follow this instruction may and will be cause for video failure. Any questions, please call our office during normal business hours at 610-694-8680.

By signing below, you are acknowledging that you have read and understand the instructions and if you have any questions about the video procedure, you have contacted the Authority for answers.

Contractor Signature: _____ Date: _____

Drop of paperwork and flash drive(s) to:
4774 Saucon Creek Road, Center Valley, PA 18034